BRUHAT BANGALORE MAHANAGARA PALIKE

Executive Engineer, Rajarajeshwarinagara Division, Rajarajeshwarinagara Zone, Bangalore

MODIFIED SCHEDULE-B

Name of Work: Improvement and Maintenance of S.W.M in JP Park in Ward No.17

Sl.No	App. Qty	Description	Unit	Approved Rates quoted by Sri.Ishwar N Naik	
				In Figures	In Words
1	0.00	KSRRB M200-12.1. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. i) Lime /Cement Concrete. I. By Manual Means: A. Lime Concrete, cement concrete grade M-10 and below. MORTH Specification No. 202 -do- C. Prestressed / Reinforced cement concrete grade M-20 above (P.139, It.No.18.19)	Cum	1600.00	Rupees One Thousand Six Hundred Only
2	13.98	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P. 13, It.No.4.6)	Cum	5459.00	Rupees Five Thousand Four Hundred Fifty Nine Only
	24.57	.-do- Qty Above 125%		5456.51	
3	0.00	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineer-in - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) including cost of materials, labour, HOM complete as per specifications. (P. 266, It.No.37.2)	Mtr	865.00	Rupees Eight Hundred Sixty Five Only
4	0.00	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint, including cost of materials, labour, HOM complete as per specifications. (P. 266, It.No.37.4)	Mtr	410.00	Rupees Four Hundred Ten Only

Scanned with CamScanner

Sl No	App. Qty	Description	Unit	Approved Rates quoted by Sri.Ishwar N Naik	
				In Figures	In Words
5	0.00	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint, including cost of materials, labour, HOM complete as per specifications. (P. 266, It.No.37.3)	Sqm	720.00	Rupees Seven Hundred Twenty Only
6	13.98	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH -100/ Chapter 1 (P. 136, It.No.17.1)	Cum	90.00	Rupees Ninety Only
	261.03	.-do- Qty Above 125%		96.01	Rupees Ninety Six And Paise One Only
		EIRL			
E-1	221.40	Removing & Refixing stone slabs of drains and pointing in C.M (1:3) (P. 27, It.No.5.33	Sqm	105.67	Rupees One Hundred Five And Paise Sixty Seven Only
E-2	246.00	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (P. 143, It.No.19.1)	Cum	130.83	Rupees One Hundred Thirty And Paise Eighty Three Only
E-3	328.00	KSRB 5-14: Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications. KBS No.5.4 - do - with solid concrete blocks of size 400x200x200mm (P. 27, It.No.5.26.1)	Sqm	968.12	Rupees Nine Hundred Sixty Eight And Paise Twelve Only
E-4	147.60	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. - do - 10 cms thick (P. 27, It.No.5.31.2)	Sqm	917.80	Rupees Nine Hundred Seventeen And Paise Eighty Only
E-5	2050.00	KSRB 5-9 : Providing chamfering edges to stone slab 2.5 cms. Wide as per specifications. (only chamfered length shall be recorded) KBS 5.1.13 (P. 26, It.No.5.22)	Rmt	58.37	Rupees Fifty Eight And Paise Thirty Seven Only
E-6	369.00	KSRB 5-8.1 : Providing one line dressing to granite stone slab / granite stone masonry as per specifications. KBS 5.1.13 (P. 26, It.No.5.17)	Sqm	902.71	Rupees Nine Hundred Two And Paise Seventy One

Kadibasappa R
Signature of the Contractor

Executive Engineer
RR Nagara Division, RR Nagara Zone
BBMP, Bangalore

Scanned with CamScanner